

1 EMPLOYMENT SERVICES

- The initial building inspection is included
- Building inspection scheduled on client's indication.
- For the approval of the building inspection, the following requirements must be met
- Not found ready construction site by building inspector or Kroftman, re-inspection at customer's expense.
- Cost (€500) re-inspection is for the customer.
- Assembly appointment only after approval of the building site.
- Assembly appointment at least 4 weeks after approved building inspection.

2 SOIL

Concrete anchors

Concrete slabs Concrete Floor Concrete ring

Grounding pins

Asphalt Streetwork Collapsed Earth/ rubble/other

Spacing
Max. 6cm between edge of concrete foundations and the base rail.

Base rail max. 6cm Concrete foundation

Concrete ring foundation
In accordance with dimensions construction drawing Kroftman.

Outstanding objects
No pins, cables, tubes at the location of baserail from concrete protruding.

< 1cm

> 1cm

Descending
Slope max. 1 cm per meter, with a max. of 10 cm over length of the building.

max. 5mm

Irregularities max. 5 mm

Hollow, convex or concave surface not allowed

No interfering underground utilities below mounting points
No items protruding into, under or from the foundation (conduits, sewer pipes and/or lightning rods).

3 SITE REQUIREMENTS

Construction site
2 times the area of the hall and 1.5m of free movement area.

Workspace
1.5 meters clearance around the building with a plain surface.

Materials
Unloading point at a maximum distance of 10 meters from the construction site..

4 WORKING FACILITIES

These facilities must be indicated:

Electricity
16 Amps

Sanitary
Toilet, water

5 LOCATION AMENITIES

These facilities should be in place:

Supply & unloading possibilities
max. 46 tons

Location for waste

Location for electricity

Location to unloading

Location for rental equipment